

COUNTY OF LAKE  
Department of Public Works  
255 North Forbes Street  
Lakeport, CA 95453

CHANGE ORDER NO: **3**

DATE: December 4, 2025

BID NO.: 24-39

PROJECT: **Proj Name: 2024 Pavement Rehabilitation Project**  
**Federal Project No.**

CONTRACTOR: **Name Argonaut Constructors, Inc.**  
**Address 360 Sutton Place**  
**City, State, Zip Code Santa Rosa, Ca. 95407**

Note: These changes in no way relieve the Contractor of completing work in accordance with standards established by the Standard Specifications and Special Provisions.

ITEM NO.	DESCRIPTION	TIME EXTENSION	VALUE
1	Add Bid Item 01 Mobilization	0	\$10,000.00
2	Add Bid Item 03 Traffic Control and Construction Area Signs	0	\$11,500.00
3	Add Bid Item Prep Roads/cut conforms/tack oil (Work to be performed on Force Account Basis)	0	\$25,000.00
4	Add HMA Type A - 1450 TN (2") x \$183.00	61	\$265,350.00
		0	\$311,850.00

REQUESTED BY: Owner

REASONS: Paving pulverized/single chipped roads with 2" HMA

ORIGINAL CONTRACT WORKING DAYS:	100	Days
TIME EXTENSION ON PREVIOUS CHANGE ORDER(S):	15	Days
TIME EXTENSION FOR THIS CHANGE ORDER:	61	Days
REVISED CONTRACT WORKING DAYS:	176	Days

ORIGINAL CONTRACT AMOUNT:	\$5,113,696.75
AMOUNT PREVIOUS CHANGE ORDERS: (Additions)	1,477,626.93
AMOUNT PREVIOUS CHANGE ORDERS: (Deletions)	-449,232.30
AMOUNT THIS CHANGE ORDER:	311,850.00
REVISED CONTRACT AMOUNT:	\$6,453,941.38

ACCEPTED: CONTRACTOR

By: _____	_____	_____
	Name and Title	Date

RECOMMENDED:

By: _____	Interim Public Works Director	12/9/25
Department of Public Works	Name and Title	Date

APPROVED: OWNER

By: _____	_____	_____
Board of Supervisors	Name and Title	Date

<u>Biditem</u>	<u>Description</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Bid Total</u>
89501	MOBILIZATION / NOTIFICATIONS	1.000	LS	10,000.00	10,000.00
89502	TRAFFIC CONTROL	1.000	LS	11,500.00	11,500.00
89503	PREP ROADS/CUT CONFORMS/TACK OIL (FA)	1.000	TM	25,000.00	25,000.00
89504	FINAL PAVING (PER TN)	1,450.000	TN	183.00	265,350.00
Bid Total =====>					\$311,850.00

Street Name	Chip seal roads to be paved	Chip seal roads to be paved	Theoretical Tonnage at 160 #/SF
	Adjusted QTY (SY)	SQ Footage	.17' depth
ADAMS SPRINGS COURT	469	4221	57
ADAMS SPRINGS RD.	4820	43380	590
ADAMS SPRINGS RD.	2582	23238	316
CAROLYN DRIVE	2588	23289	317
CREEK VIEW DRIVE	2264	20375	277
COSTELLO WAY	1334	12010	163
ELLIOT DR	5404	48640	662
HOGAN HILL LANE	2089	18800	256
JONES COURT	833	7500	102
LASSEN DR.	2811	25300	344
PALMER DR	3682	33138	451
PALMER COURT	1459	13127	179
PAMELA DRIVE	1388	12495	170
PRATHER COURT	420	3780	51
PRATHER WAY	3022	27200	370
REGINA WAY	1648	14828	202
ST. HELENA DRIVE	3809	34280	466
BROOKSIDE DR (Not paved)	3946	35514	483
DOVE DR	1282	11536	157
ENTRANCE ROAD	763	6868	93
FOREST LAKE DR (Not paved)	740	6660	91
GROUSE RD	767	6900	94
QUAIL DR	1342	12080	164
SUMMIT DR (Not paved)	3183	28645	390
SUGAR PINE (Not paved)	2920	26280	357
TOTAL	55565	500083	6801

HMA quantity for remaining roads	1321
10% Contingency	132
Total	1453

Total Tonnage (+10%)	1450 TONS
----------------------	-----------