

**SPECIFICATIONS FOR
LAKE COUNTY CALIFORNIA
MOBILE MEDICAL UNIT
HLE 23-10185-R0**

1. CHASSIS/BODY:

- i. 2023 Freightliner S2C
- ii. Regular Cab
- iii. 4X2
- iv. Diesel
- v. HLE Purpose Built Body

2. CONVERSION:

1) PRIVATE CONSULTATION ROOM:

- i. Fully insulated for sound and heat
- ii. Wheelchair lift located in rear ADA accessible bathroom
- iii. Medical grade refrigerator
- iv. Medical grade freezer

2) IMMUNIZATION STATION:

- i. Three (3) immunization stations
- ii. Each station will include patient seating
- iii. A small desk workstation for staff
- iv. Overhead Cabinet at each station
- v. Doctors stool at each station
- vi. Network Cabling
- vii. Storage space
- viii. Hospital grade privacy curtain

3) LAB AREA:

- i. Lab area to have Combination Medical Grade Fridge and Freezer
- ii. Stainless Steel Handwash Sink
- iii. Network Cabling ports
- iv. Storage for Supplies.

4) Cabinetry - Construction:

- i. All interior cabinets shall be constructed using cabinet grade, hardwood veneer plywood.
- ii. Storage Cabinets will be constructed according to final floorplan.
Drawers and Cabinets will include flush mounted lockable latches.

**SPECIFICATIONS FOR
LAKE COUNTY CALIFORNIA
MOBILE MEDICAL UNIT
HLE 23-10185-R0**

5) Restroom:

- i. Restroom to be ADA Accessible
- ii. Power Roof Vent
- iii. White China Toilet
- iv. Toilet Paper Dispenser
- v. Grab Handles
- vi. Stainless steel sink with faucet ADA Accessible
- vii. Soap & Paper Towel Dispenser

6) Ceiling:

- i. Ceiling will be made of Fiberglass Reinforced Plastic (FRP). Ceiling will be covered with 3/8" plywood then covered with 2.7mm FRP panel.

Ceiling height will be minimum of 85 inches.

7) Emergency Egress:

- i. An emergency egress shall be provided, per the vehicles final floor plan.

8) Floor Covering:

- i. High Quality commercial grade flooring to be installed

9) Electrical, Generator and HVAC

- i. Electrical Package with Custom Wiring Diagram
- ii. Upfit of Coach Wiring and Switches
- iii. LED Lighting
- iv. (1) 8.0 kw 120/240 Commercial Diesel Generator or Equal
- v. 120v/12v Wiring Systems
- vi. 110 Breaker Box
- vii. 12v Fuse Panel
- viii. Converter Charger 80 amp
- ix. 50 Amp Shore Power
- x. House Batteries (2) Group 24
- xi. 200 Amp Isolator
- xii. Exterior GFI Outlet near Curside Entry Door

**SPECIFICATIONS FOR
LAKE COUNTY CALIFORNIA
MOBILE MEDICAL UNIT
HLE 23-10185-R0**

- xiii. (2) 15,000 BTU Rooftop A/C's with 12,000 BTU Heat Pump

10) Lighting, Interior:

- i. 12 Volt LED Lights shall be installed throughout the interior of the unit.

11) Lighting, Exterior:

- i. One (1) LED porch light shall be installed above the curbside entry door.

12) Exterior:

- i. Exterior Power Awning
ii. Removable Solera Awning Patio Room to work as Waiting Room
iii. Exterior TV set inside weather proof compartment to facilitate patient education

13) Wifi Connectivity Package:

- i. To install Cradlepoint IBR900-600M with roof top antenna

14) Safety Package:

- i. Carbon Monoxide Detector
ii. Smoke Detector
iii. 5lb. Fire Extinguisher
iv. Back up Alarm
v. DOT Reflective Triangle Kit
vi. First Aid Kit
vii. Tri-View Camera Sysytem (Left Turn Signal, Right Turn Signal & Rear View Camera. Monitor In Cab for Driver)

15) Warranty:

- i. HLE Conversion 3 years/ 36,000 Miles
ii. HLE Purpose Built Body 5 years/100,000 Miles
iii. Generator 2 years / 2,000 Hours
iv. All other components are warrantied through respective manufacturer.

16) Optional Equipment:

- viii. 4-Point Automatic Leveling Jacks for leveling unit.
ix. Full Exterior Graphics Wrap