



Legend

- KS = kitchen sink
- WH = water heater
- AP = access panel
- Sh = shower
- WC = water closet
- WM = washing machine
- L = lavatory
- AAV = air admittance valve
- MF = manifold

Notes

- 1) Drain positions are from finished wall (3/8" plaster)
- 2) Vents exit exterior wall, under awning, w/AAV
- 3) Toilet (WC) drain 3" diam, capped both ends
- 4) Supply lines are PEX-A (aka Uponor)
- 5) 3-way valve, backwater valve, sewer hookup are option for future owner
- 6) Water heater (WH) is tankless electric (Rheem 11 kW)
- 7) Supply lines distributed with "home run" manifold
- 8) Fire sprinkler system shown separately

Description: Plumbing, plan view Scale: 1/4" = 1'

Project: Torbet home

Drawn by: Eric Torbet

Date: 7-28-2023