



September 20, 2018
Lake County Special Districts Administration
230A Main Street
Lakeport Ca, 94543
Attn: John Sparkes

We at Industrial Electrical Company are pleased to offer you a quote for an Emergency Standby Towable Generator per the spec provided. Freight to Middleton Ca is included in Quote. **Tax is Not Included in Quote.**

Qty (1) Kohler **125REOZJG** diesel powered generator set, rated for standby duty at 128kw, .8PF, 160KVA, 480v, 3 phase, 4 wire, 60hz, 1800RPM, mounted in an outdoor rated weatherproof sound attenuated enclosure with 298 gallon subbase diesel fuel tank rated for 24 hours at full load (**see spec sheet for further details**) including supply/install of (1) 20' 2/0-4 conductor Tuype W 2kv 90c cord and (1) Appleton AP20034E 200amp 480v, 3 phase, 3 wire plus ground cord cap..... **\$36,725.00**

Startup Includes: Install 12-Volt Battery (**Supplied by Mfg**), Inspect Generator and Transfer Switch (if applicable), perform building load test with available building load at time of startup (**customer responsible to provide fuel, cable and connection to building, resistive load bank testing can be provided additional to pricing provided**), Program Transfer Switch as needed (if applicable). Perform 1hr Training to available personnel at time start-up is performed.

Start-Up..... **\$1,200.00**

Exclusions from this quote:

Quote based on specifications supplied 8/27/18
Fuel is not included
Offloading by Others
Sizing Provided by Others
All applicable permits and fees Not Included
Any and All Installation
Tax is Not Included

Quote valid for 60 days
Best regards,

Rich Hodge
Industrial Electrical Company
Service Manager
PH: (209) 422-6075
FX: (209) 527-8095
Cell: (209) 652-8282
rhodge@iecmail.com



YOUR POWER SYSTEMS SPECIALISTS

P.O. Box 10083 Reno, NV 89510-0083 TEL (775) 331-4151 FAX (775) 331-4977
August 30, 2018 1395 Spice Island, Sparks, NV 89431 email sales@nevadaenergysystems.com

LAKE COUNTY SPECIAL DISTRICTS

Attn: John Sparkes

John.sparkes@lakecountycal.gov

Subject: 125KW Standby Generator

Dear John:

We are pleased to submit our quotation to provide the following equipment:

One (1) GILLETTE Generator Model SPJD1250-3-4 JOHN DEERE DIESEL engine generator set rated 125KW 480 Volt, three phase, 60 HZ., 1800 RPM (to pick up 2 ea. 47 HP pumps) complete with all standard equipment and including the following accessories:


- 105 Degree rise PMG generator
- Electronic governor
- Jacket water heater with isolation ball valves with shore power plug
- Oil and coolant drain extension
- Battery, rack and cables
- 6 Amp float battery charger with battery kill switch
- NFPA110 digital controller with display of engine safeties, gauges and metering with communications.
- Exhaust silencer, stainless steel flexible exhaust connection & rain cap installed within the enclosure.
- 24 hr. (206)gal. base mounted, UL listed, double walled fuel tank with low / high fuel level alarm.
- 200 Amp mainline circuit breaker with shunt trip and auxiliary contacts
- 2 year warranty
- Level II Sound attenuated weather protective enclosure painted beige
- Isolators
- 2 year warranty
- Factory testing
- Initial start up and testing @ jobsite
- (1) O&M manual
- 200 Amp Appleton Receptacle to match customer's Appleton plug.

TOTAL NET PRICE FOR JOBSITE.....\$39,978.00

Terms: Net 15 days. Sales tax is not included and shall be added if applicable. Delivery is running approx. 8-10 weeks at this time.

We appreciate this opportunity to submit our quotation for your consideration, and look forward to working with you.

Sincerely,
NEVADA ENERGY SYSTEMS, INC


Sandy Todaro
Sales Representative





John Sparkes
Lake County Special Districts

Subject: 125KW Standby Generator

Dear John:

We are pleased to submit our quotation to provide the following equipment:

One (1) GILLETIE Generator Model SPJD1250-3-4 JOHN DEERE DIESEL engine generator set rated 125KW 480 Volt, three phase, 60 HZ., 1800 RPM (to pick up 2 ea. 47 HP pumps) complete with all standard equipment and including the following accessories:

- 105 Degree rise PMG generator
- Electronic governor
- Jacket water heater with isolation ball valves with shore power plug
- Oil and coolant drain extension
- Battery, rack and cables
- 6 Amp float battery charger with battery kill switch
- NFPA110 digital controller with display of engine safeties, gauges and metering with communications.
- Exhaust silencer, stainless steel flexible exhaust connection & rain cap installed within the enclosure.
- 24 hr. (206)gal. base mounted, UL listed, double walled fuel tank with low / high fuel level alarm.
- 200 Amp mainline circuit breaker with shunt trip and auxiliary contacts
- 2 year warranty
- Level II Sound attenuated weather protective enclosure painted beige
- Isolators
- 2 year warranty
- Factory testing
- Initial start up and testing @ jobsite
- (1) O&M manual

TOTAL NET PRICE FOR JOBSITE\$41,556.00

Terms: Net 15 days. Sales tax is not included and shall be added if applicable. Delivery is running approx. 8-10 weeks at this time.

We appreciate this opportunity to submit our quotation for your consideration, and look forward to working with you.

Sincerely,

Jim Laskowski
Manager Industrial Electric Motors